



**Water. Works.**



est. 1980

12 months or 18 months from delivery, whichever comes first

**Total Price Including Installation..... \$252,900.00**

**Valdosta Mud Creek WPCP Or-Tec Installation Scope of Work:**

1. Mobilize to Valdosta Mud Creek WPCP
2. Prep current bar screen for removal
3. Prep compactor for removal
4. Provide crane and rigging services
5. Remove current screen and set aside
6. Remove compactor and set aside
7. Install new Ortec Compactor
8. Install new Ortec Microbar Screen
9. Make all piping connections
10. Remove current Bar Screen Control Panel
11. Install new Ortec MBS Control Panel in same location
12. Make all electrical connections to new screen, compactor, and panel using existing wire and conduit
13. Perform Startup Services

**Exclusions**

- Offloading of new equipment
- Running new electrical service
- Modifications to existing channel
- Disposal of old equipment

Notes:

Submittal lead time: 10 business days from receipt of purchase order

Delivery: 14 - 20 weeks upon written approval of submittals

Prices quoted are valid for 90 days

Standard Terms and Conditions Attached